September 23, 2022

10564 W 63rd Ln
Arvada CO 80004

Re: Duct leakage test for 10564 W 63rd Ln

To whom it may concern:

E3 Power performed a Duct leakage test on system in the above mentioned building on September 23, 2022 at 10:30 AM. The duct system serves approximately 1560 square feet. The maximum duct leakage would be 62 CFM or less @ -25 pascals. The total duct leakage measurement was 43 CFM @-25 pascals. The duct system meets the air tightness requirement of 4 CFM per 100 square feet of area served or less and is compliant with code.

Please let me know if I can be of further assistance to you.

Sincerely,

Jessica W. Kurela

Digitally signed by Jessica W. Kurela
Date: 2022.09.23 13:30:32 -06'00'

Jessica W. Kurela (e3 power)
303-292-1233
Building Analyst (BPI)